

Provision of New Village Car Park on Village Hall Playing Fields

As discussed I have put together a quote for the excavation of approx 450 sqm of turf and soil at the edge of the football field for an ACO ground tile car parking area.

The total cost for this project is: £25,500.00

This price includes:

- Excavator hire (15 days)
- Dumper hire (10 days)
- Roller hire (10 days)
- Diesel (for plant)
- Safety fencing hire (15 days)

- ACO Ground Tiles (2000 pcs)
- Type 1 stone (200 ton)
- Limestone (60 ton)
- Woven Geo textile roll (400 sqm)
- Removable metal parking post.
- Metal chain.

- Labour (15 days x 2)

I would estimate the time scale for this project to completed will be three weeks however, I will allow for four weeks just in case of bad weather.